# ANN ARBOR PUBLIC SCHOOLS THURSTON ELEMENTARY SCHOOL 2300 PRAIRIE STREET ANN ARBOR, MICHIGAN

### **REQUIRED STATEMENTS**

### **PROJECT DESCRIPTION**

SITE WORK AS IT RELATES TO THE THURSTON ELEMENTARY SCHOOL INCLUDES THE FOLLOWING:

THE WORK ON THE SUBJECT SITE CONSISTS OF THE INSTALLATION OF (4) MODULAR UNITS THAT WHEN ASSEMBLED TOGETHER WILL CREATE A 4,844 SQUARE FOOT (4) CLASSROOM BUILDING WITH RESTROOMS, STEPS, RAMPS AND COVERED WALKWAYS. THE MODULAR BUILDING WILL BE TIED INTO EXISTING WATER, SEWER, AND ELECTRICAL. (REFER TO SHEET #4)

### **NATURAL FEATURES IMPACT**

### WETLANDS, SOIL EROSION, AND FLOOD ZONE

NO WETLANDS, WOODLANDS, OR FLOOD-PLAIN WILL BE IMPACTED BY THE PROJECT. THE PROJECT DOES NOT CONTAIN STEEP SLOPES OR NEGATIVE IMPACT TO WATER RESOURCES.

### **LANDMARK TREES**

TREES WITHIN THE FOOTPRINT OF THE MODULAR BUILDING WILL BE RELOCATED. NEW LOCATION WILL BE DETERMINED BY THE OWNER AT A LATER DATE.

### **POLLUTION OR CONTAMINATION ON SUBJECT SITE**

THERE ARE NO KNOWN POLLUTION FOR CONTAMINATES ON THE SUBJECT SITE.

### **SOIL EROSION AND SEDIMENTATION PLAN**

THE STATE OF MICHIGAN DEPARTMENT OF LICENSING AND REGULATORY AFFAIRS BUREAU OF CONSTRUCTION CODES / PLAN REVIEW DIVISION DOES NOT REQUIRE SOIL EROSION AND SEDIMENTATION CONTROL, GENERALLY WHEN LESS THAN ONE ACRE IS DISTURBED. THE DISTURBED AREA WILL BE LESS THAN ONE ACRE.

### **CONSTRUCTION STORM WATER PROGRAM**

TO BE DETERMINED.

### **PROJECT MANAGEMENT**

### TRAFFIC IMPACT

TO BE DETERMINED.

### **DRIVEWAYS**

NO EXISTING DRIVEWAYS WILL BE IMPACTED ON THE SUBJECT SITE.

### **NOISE CONTROL**

THE MAJORITY OF THE CONSTRUCTION ACTIVITIES ARE DONE OFF SITE AT THE MODULAR BUILDING MANUFACTURER'S LOCATION. THE EQUIPMENT USED ON THE SUBJECT SITE WILL CONSIST OF A BACK HOE, TRUCK, CONCRETE MIXER, GENERATOR, COMPRESSORS, POWER SAWS, AND ELECTRIC DRILLS. THE AVERAGE SOUND LEVEL WILL BE WILL BE LESS THAN THE OSHA (AT WORKERS EAR) LEVEL OF 90.

## LEGAL DESCRIPTION

BEG W 1/4 COR SEC 14, T2S R6E TH N 89 DEG 08 MIN 20 SEC E 660.75 FT TH S 1 DEG 12 MIN E 1591.32 FT TH S 89 DEG 08 MIN 20 SEC W 610.0 FT TH NLY 101.96 FT ALG ARC OF CIR CURVE CONCAVE SW R=6602.95 FT CHORD N 29 DEG 12 MIN 20 SEC W 101. 84 FT TH N 34 DEG 03 MIN W 5.62 FT TH N 1 DEG 11 MIN 40 SEC W 1496.99 FT TO POB PART W 1/2 SEC 14 T2S R6E ALSO OUTLOT C NORTH CAMPUS HEIGHTS ALSO LOTS 121 122 123 124 & 125 NORTH CAMPUS HEIGHTS NO 3 EXC BEG AT NW COR OF SD LOT 125 TH NE 144.09 FT TH S 106 FT TH WLY TO POB

ANN ARBOR PUBLIC SCHOOLS

2555 S. STATE ST.

ANN ARBOR, MI 48104

734.995.2043

ATTN: JENNIFER HEIN

### OWNER'S ARCHITECT

MITCHELL AND MOUAT ARCHITECTS
113 S. FOURTH AVE.
ANN ARBOR, MI 48104
734.662.6070

ATTN: KEVIN STANSBURY

GENERAL CONTRACTORS ARCHITECT
GREGORY NOETH ARCHITECT
1790 SARATOGA AVE.
CLEVELAND, OH 44109
216.789.2086

ATTN: GREG NOETH

GENERAL CONTRACTOR
INNOVATIVE MODULAR SOLUTION
30803 OLD US HWY 33
ELKHART, IN 46516
574.830.8237
ATTN: JASON SHANNON

MICHIGAN DESIGN CODES:

2014 MICHIGAN ELECTRICAL CODE /2014 NEC

2012 MICHIGAN BUILDING CODE (IBC)

2012 MICHIGAN MECHANICAL CODE (IMC)

2012 MICHIGAN PLUMBING CODE (IPC)

2009 MICHIGAN UNIFORM ENERGY CODE 10A 2007 ASHRAE

AMERICAN WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES

MICHIGAN SCHOOL BULLETIN #412 (FOR CLASSROOMS ONLY)

### **DRAWING INDEX**

SHEET # DESCRIPTIION

- COVER SHEET
- 2. OVERALL SITE PLAN
- 3. EXISTING CONDITIONS & REMOVAL PLAN
- 4. OVERALL UTILITY PLAN
- 5. EROSION CONTROL PLAN
- 6. EROSION CONTROL NOTES & DETAILS
- 7. PROJECT LANDSCAPE PLAN
- 8. FIRE PROTECTION PLAN
- 9. BOUNDARY SURVEY

Local Governmental Agency to Complete This Section							
ENVIRONMENTAL CONTROL APPROVALS							
	REQUIRED?		APPROVED	DATE	NUMBER	ВҮ	
A - Zoning	□Yes	□ No					
B - Fire District - (Refer to Fire Prevention Plan Sheet #8)	□ Yes	□ No					
C - Pollution Control - (Refer to Notes on Cover Sheet # 1)	□ Yes	□ No					
D - Noise Control - (Refer to Cover Notes on Sheet #1)	□ Yes	□No					
E - Soil Erosion - (Refer to Erosion Control Plan Sheets # 5 & 6)	□ Yes	□ No					
F - Flood Zone - (Refer to Cover Notes on Sheet # 1)	□ Yes	□ No					
G - Water Supply - (Refer to Utility Plan Sheet # 4)	□ Yes	□ No					
H - Sewer - (Refer to Cover Notes on Sheet # 4)	□ Yes	□ No					
I - Variance Granted	□ Yes	□ No					
J - Other	□ Yes	□ No					

# COVER SHEET SCALE:NONE

PUBLIC SCHOOLS


EMENTARY SCHOOL

R SHEET


Innovative Modular


Ekhort, 10 46516


Estimate Office: 15 corporate Office: 16 corporate Offi





















PERMANENT MAINTENANCE TASKS AND SCHEDULE

NOTE: TEMPORARY INLET SEDIMENT FILTER TO BE INSTALLED ON ALL PAVED CATCH BASINS OR STORM INLETS. INLET FILTER TO BE SIMILAR TO "STREAMGUARD" AS MANUFACTURED BY STORMWATER SERVICES CORPORATION (206-767-0441) OR "SILTSACK" AS MANUFACTURED BY ATLANTIC CONSTRUCTION FABRICS, INC.; (800-448-3636). CLEAN FILTER AS NEEDED.

DUMP STRAPS -



CONSTRUCTION SEQUENCE	SOIL EROSION CONTROL MEASURES
PRIOR TO CONSTRUCTION	<ul> <li>PRE-GRADING MEETING WITH ANN ARBOR SOIL EROSION CONTROL STAFF</li> <li>IDENTIFY CONSTRUCTION LIMITS</li> <li>INSTALL SILT FENCE</li> <li>INSTALL CURB AND GUTTER INLET FILERS</li> </ul>
CONSTRUCT UTILITIES	<ul> <li>MAINTAIN EXISTING CONTROLS</li> <li>DETENTION FACILITIES MUST BE INSTALLED AND FUNCTIONING PRIOR TO THE ISSUANCE OF ANY BUILDING PERMITS.</li> </ul>
PAVE DRIVEWAY & PARKING LOTS	<ul> <li>MAINTAIN EXISTING CONTROLS</li> <li>INSTALL CURB AND GUTTER INLET FILTERS</li> </ul>
DURING BUILDING CONSTRUCTION	<ul> <li>SILT FENCE SHALL BE MAINTAINED ON DOWN SLOPE SIDE OF LOT TO CONTROL RUNOFF</li> </ul>
AFTER BUILDING CONSTRUCTION IS	<ul> <li>SEED AND MULCH OR SOD AREAS THAT HAVE NOT TAKEN</li> </ul>

- REMOVE SILT FENCE IF SEED OR SOD

SEED AND MULCH (SOD SLOPES > 3:1)
 DISTURBED AREAS

- MAINTAIN EXISTING CONTROLS

MAINTAIN EXISTING CONTROLS

- CLEAN OUT INLET SUMPS

RE-SOD OR SEED MULCH AREAS THAT HAVE NOT TAKEN

- REMOVE CURB AND GUTTER INLET


FINE GRADE SITE


CLEAN UP SITE

AFTER DISTURBED AREAS


HAVE STABLE VEGETATION


COMPLETED






SCALE:NONE





- 1. THE CONCRETE WASHOUT AREA SHALL BE INSTALLED PRIOR TO ANY CONCRETE PLACEMENT ON THIS PROJECT. 2. SIGNS SHALL BE PLACED AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CONCRETE WASHOUT. 3. THE CONCRETE WASHOUT AREA WILL BE REPLACED AS NECESSARY TO MAINTAIN CAPACITY FOR WASTE CONCRETE AND
- WASHOUT RESIDUE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT AN APPROVED WASTE SITE.
- DO NOT MIX EXCESS AMOUNTS OF FRESH CONCRETE OR CEMENT ON-SITE.
   DO NOT WASH OUT CONCRETE TRUCKS INTO STORM DRAINS, OPEN DITCHES, STREETS, OR STREAMS. AVOID DUMPING EXCESS CONCRETE IN NON-DESIGNATED DUMPING AREAS.
- 8. LOCATE WASHOUT AREA AT LEAST 50' (15 METERS) FROM STORM DRAINS, OPEN DITCHES, OR WATERBODIES 9. WASH OUT WASTES INTO THE OUTPACK WASHOUT AS SHOWN WHERE THE CONCRETE CAN SET, BE BROKEN UP, AND THEN

### OR APPROVED EQUAL CONCRETE WASHOUT SYSTEM



### STORM WATER MANAGEMENT SYSTEM MAINTENANCE PLAN

- Responsibility for Maintenance:
- (a) During construction, it is the contractor's responsibility to perform the maintenance.
- (b) Following construction, it will be the responsibility of the Ann Arbor Public School's facility staff
- Maintenance Tasks and Schedule

for any necessary sediment removal.

- (a) See the chart on this sheet. The chart describes maintenance tasks to be performed by the
- (b) Immediately following construction, the contractor will have the stormwater management system inspected by an engineer to verify grades of the detention and filtration areas and to make recommendations

### SOIL EROSION AND SEDIMENTATION CONSTRUCTION NOTES:

- 1. ALL SOIL EROSION CONTROL MEASURES SHALL COMPLY WITH THE CURRENT CITY OF ANN ARBOR ORDINANCES, WASHTENAW COUNTY STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, AND STATE OF MICHIGAN "SOIL EROSION AND SEDIMENTATION CONTROL ACT" (ACT NO. 347).
- INSTALL THE MUD TRACKING MAT, THE SILT FENCE AND TREE PROTECTION FENCES AS 3. THE ACTUAL LOCATION OF THE MUD TRACKING MATS MAY BE ADJUSTED BY THE

2. PRIOR TO COMMENCING EARTHMOVING OPERATIONS, THE GRADING CONTRACTOR SHALL

- CONTRACTOR TO MATCH CONTRACTOR'S OPERATIONS AND FIELD CONDITIONS BUT ONLY IF APPROVED BY THE ENGINEER. 4. ANY LAWN AREA WHICH WILL HAVE A SLOPE OF 3:1 OR STEEPER (3 FT MEASURED HORIZONTALLY AND 1 FT MEASURED VERTICALLY) SHALL BE SODDED AND PEGGED OR
- SEEDED AND MULCHED USING A SOIL EROSION CONTROL FABRIC OR BLANKET. HYDROSEEDING MAY BE USED IN LIEU OF SEED AND MULCH OR SOD WHERE SLOPES ARE FLATTER THAN 3:1.
- 5. ALL DISTURBED AREAS, EVEN WHERE FUTURE PAVEMENT AND BUILDINGS ARE PROPOSED, ARE TO BE RE-VEGETATED PER COUNTY STANDARDS FOR TEMPORARY SEEDING.
- 6. ALL RIPRAP SHALL BE PLACED OVER NON-WOVEN FILTER FABRIC.
- 7. ALL EXISTING AND/OR PROPOSED INLETS AND CATCH BASINS WITHIN THE PROJECT WILL HAVE POSITIVE COLLECTION SEDIMENT FILTERS INSTALLED. THESE FILTERS WILL BE MAINTAINED UNTIL ALL DISTURBED AREAS ARE STABILIZED. "SILTSACK", AS MANUFACTURED BY ACF ENVIRONMENTAL (OR APPROVED EQUAL) MAY BE USED.
- ALL UNPAVED DISTURBED AREAS IN BACK OF CURB LINES WILL BE TOPSOILED, SEEDED, AND MULCHED. SLOPES THAT ARE 3:1 OR STEEPER WILL BE SODDED OR SEEDED AND MATTED WITHIN 5 DAYS OF ESTABLISHING THE FINAL GRADES.
- 9. THE CONTRACTOR WILL MAINTAIN ALL NECESSARY SOIL EROSION CONTROL DEVICES UNTIL SOIL STABILIZATION HAS OCCURRED.
- 10. APPROPRIATE EMERGENCY ACCESS WILL BE PROVIDED AND DOCUMENTED PRIOR TO
- 11. THE CONTRACTOR WILL BE RESPONSIBLE FOR BALANCING THE EARTHWORK AND FOR TRUCKING OFF AND LEGALLY DISPOSING OF ALL EXCESS SOIL MATERIAL.
- 12. SEE THE SOIL EROSION CONTROL PLANS AND LANDSCAPE PLANS FOR LOCATIONS AND TYPES OF SEED AND MATTING, OR SEED.
- 13. SOD MAY BE USED WHEREVER SEEDING IS INDICATED EXCEPT IN AREAS REQUIRING
- 14. DRAINAGE FROM ALL PAVEMENT AND ROOFS WILL BE DIRECTED TO THE ON-SITE STORM
- 15. THE ESTIMATED COST TO STABILIZE THE AREA OF DISTURBANCE IS \$3,000.00.

### SOIL EROSION AND SEDIMENTATION PLAN


THE STATE OF MICHIGAN DEPARTMENT OF LICENSING AND REGULATORY AFFAIRS BUREAU OF CONSTRUCTION CODES / PLAN REVIEW DIVISION DOES NOT REQUIRE SOIL EROSION AND SEDIMENTATION CONTROL, GENERALLY WHEN LESS THAN ONE ACRE IS DISTURBED. THE DISTURBED AREA WILL BE LESS THAN ONE ACRE.


- 1. ALL SILT FENCES SHALL BE MAINTAINED THROUGHOUT THE DURATION OF THE PROJECT. IF THE DEPTH OF SILT AND SEDIMENT COMES TO WITHIN 12 INCHES OF THE TOP OF ANY SILT FENCE AT ANY TIME, ALL SILT AND SEDIMENT SHALL BE REMOVED TO ORIGINAL
- 2. ALL TEMPORARY GRAVEL FILTERS SHOULD BE ADJUSTED AS TO LOCATION PER ACTUAL FIELD CONDITIONS. THE REMOVAL OF TRAPPED SEDIMENT AND CLEANOUT OR REPLACEMENT OF CLOGGED STONE MAY BE NECESSARY AFTER EACH STORM EVENT DURING THE PROJECT.
- 3. ONLY UPON STABILIZATION OF ALL DISTURBED AREAS MAY THE SILT FENCE, AND TEMPORARY GRAVEL FILTERS BE REMOVED. ALL SEDIMENT MUST ALSO BE CLEANED OUT
- 4. PAVED AREAS MUST BE CLEANED OF ANY TRACKED MUD IMMEDIATELY FOLLOWING EACH MUD-TRACKING OCCURRENCE.
- 5. AN NPDES/NOC PERMIT FROM THE STATE OF MICHIGAN IS NOT REQUIRED DUE TO THE DISTURBED AREA BEING LESS THAN 5 ACRES.

ARCHITECT

EROSION CONTROL NOTES & DETAILS







# LEGAL DESCRIPTION REGERY J

BEG W 1/4 COR SEC 14, T2S R6E TH N 89
DEG 08 MIN 20 SEC E 660.75 FT TH S 1 DEG
12 MIN E 1591.32 FT TH S 89 DEG 08 MIN 20
SEC W 610.0 FT TH NLY 101.96 FT ALG ARC
OF CIR CURVE CONCAVE SW R=6602.95 FT
CHORD N 29 DEG 12 MIN 20 SEC W 101. 84 FT
TH N 34 DEG 03 MIN W 5.62 FT TH N 1 DEG 11
MIN 40 SEC W 1496.99 FT TO POB PART W 1/2
SEC 14 T2S R6E ALSO OUTLOT C NORTH
CAMPUS HEIGHTS ALSO LOTS 121 122 123
124 & 125 NORTH CAMPUS HEIGHTS NO 3
EXC BEG AT NW COR OF SD LOT 125 TH NE
144.09 FT TH S 106 FT TH WLY TO POB



